



Willcox High School
WRESTLING ROOM ADDITION
240 N. Bisbee Ave. Willcox, AZ 85643

ADDENDUM NO: 2
December 16, 2025

ALL CONTRACT BIDDERS OF RECORD, OWNER & CONSULTING ENGINEERS.

The following changes, additions or deletions are for the above referenced contract documents; all other conditions shall remain the same. Acknowledge receipt of this addendum by inserting its number in the "Bid Form." This addendum forms a part of the contract documents and modifies them as follows:

- ITEM 1** General Items:
1. Bid Date: The bid date is unchanged. Wednesday, January 7, 2026, 2:00 P.M. Bids must be delivered to Willcox as outlined in the specifications.
- ITEM 2** Drawings, Sheet g1.0 Cover:
- a. The deferred submittal is not applicable to this project.
 - b. The bid alternates are not applicable to this project. There is only a base bid.
- ITEM 3** Drawings, Sheet a1.2 Plans:
- a. Keynote 11.11 shall now read: The owner is responsible for moving out existing lockers prior to construction and for reinstalling.
 - b. Keynote 11.2 should point to (3) columns. The keynote reads: Provide new four sided 2" thick by 7'-0" high padded column covers. 2" thick bonded foam class A fire rated, Z clip installed. Sports field specialties or equal.
- ITEM 4** Drawings, Sheet A3.1, Roof Plan:
- a. At 6 locations, the roof deck will require repair due to the removal of the evaporative coolers and old heater flues. At each location, plan on a 36" W x 48" L repair.
- ITEM 5** Drawings, Sheet a4.0, Exterior Elevations:
- a. Keynote 7.5 shall now read: All existing metal siding, trim, gutters and downspouts shall be replaced. Refer to specification section 131250 for panel spec.
- ITEM 6** Drawings, Sheet p2.0 Plumbing:
- a. A new gas line is required. There is an existing gas main 20 feet to the Northeast. Contractor is responsible for all trenching.